

**Amendment to the Claims:**

This listing of the claims will replace all prior versions, and listings, of claims in the application.

**Listing of Claims:**

Claim 1-20 (Canceled).

Claim 21 (Currently amended). A method of assembling a blown film tower inside a building, comprising the step of:

simultaneously raising both a nip assembly and a top platform together in one lift to build the tower for blown film processing within the building, wherein the simultaneously raising step is accomplished without the use of telescoping platform supports as a part of the tower to assemble the blown film tower.

Claim 22 (Original). The method of claim 21, wherein the platform includes: hand rails.

Claim 23 (Original). The method of claim 22, wherein the platform includes: stairs.

Claim 24 (Original). The method of claim 21, wherein the platform includes: support columns for supporting a deck of the platform.

Claim 25 (Currently amended). A method of assembling a ~~blow film~~ tower for blown film processing inside an existing building for use in blown film processing, comprising the steps of:

erecting a platform supported by columns, the platform having an opening therethrough;

lifting a nip assembly mounted on a ~~support~~ base member up through the opening in the platform without the use of telescoping support members; and

attaching the ~~support~~ base member to the platform, wherein the nip assembly is used in blown film processing.

Claim 26 (Original) The method of claim 25, wherein the nip assembly is pre-attached to the support member.

Claim 27-30 (Canceled).